© 2007 COX ENGINEERING DBA CAMBRIDGEPORT AIR SYSTEMS.
THE INFORMATION CONTAINED IN THIS DOCUMENT IS PROPRIETARY TO
COX ENGINEERING COMPANY DBA CAMBRIDGEPORT AIR SYSTEMS.
THIS DOCUMENT OR THE INFORMATION CONTAINED IN WHOLE OR IN PART
MAY NOT BE ISSUED TO ANOTHER PARTY WITHOUT WRITTEN CONSENT AND
AUTHORIZATION FROM CAMBRIDGEPORT. JCI 1RCO-443 **SURE LOCK ROOF CURB** 1028507 Approval Block Drawn Date: 12/11/19 Rev. Date: \_\_\_\_\_ **SUBMITTAL** # Company: \_\_\_\_\_ Drawn By: RTO 1028507 Job Name: \_\_\_\_\_ Estimated Weight: 223 LBS. Approved By: – 121 5/8" OD ——— Notes: 117 7/8" ID ——— 25 15/16" 22 3/16' 27 7/8" INSULATED PANEL 63 7/8" S/A 80 5/8" 76 7/8" 69 9/16" R/A OD INSULATED PANEL P INSULATED PANEL **PANEL GASKET** (BY C.A.S.) COUNTER **FLASHING** 1 X 4 **WOOD NAILER** (FIELD (BY C.A.S.)~ **SUPPLIED**) ROOFING FELT (FIELD SUPPLIED) **RIGID INSULATION** (FIELD SUPPLIED): FEATURES: -CANT STRIP (FIELD SUPPLIED) Cambridgeport Mitered Corners. Gasketing Provided for Unit to Curb Sealing.
Roof Curb is Fabricated of Heavy Gauge Galvanized Steel.
Full Perimeter Wood Nailer.
Pre-Punched Holes and Hardware Included for Curb Assembly.
Roof Curb is Shipped Knocked Down.
Roof Curb is Labeled with RTU # if Applicable. 2. 3. SECTION E-E TYPICAL INSTALLED 4 Carlton Drive 5. **CURB SECTION** 1-800-648-2872 6. 7. Georgetown MA 01833 **HVAC Accessories & Engineered Systems**